

7-1-88

1 020161

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-21,011 - 0000

SW NE SW, SEC. 11, T 32 S, R 31 W

1650 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name Dreitz Well # 1-11

Operator: Shepler & Thomas, Inc.

County Seward 195.00

Name & Address P.O. Box 1162

Well Total Depth 6000 feet

Liberal, KS 67905-1162

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1629

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A  old hole

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address 620 South Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9 a.m. Day: 1 Month: 7 Year: 19 88

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5999' Perfs at 4888-92, 5715-20, 5909-11'

1st plug set CIBP at 4840' with 1 sx cement on top,

2nd plug pump 40 sx cement at free point,

3rd plug at 1660' with 40 sx cement,

4th plug at 680' with 30 sx cement, 5th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 1 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5000', set CIBP at 4840',

2nd plug pumped 50 sx cement at 1660',

3rd plug pumped 30 sx cement at 750',

4th plug pumped 10 sx cement at 40-0'.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 7 1988

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 3015' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

(if applicable) observe this plugging.

INVOICED

DATE 7-21-88

Signed Gene R. Barber  
(TECHNICIAN)

INV. NO. 21546

7-1 AUG 3 1988