

To: 1 100082
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 175-21,066 - 0000
NE NW SE, SEC. 11, T 32 S, R 31 WXX
2490 feet from S section line
1590 feet from E section line

11-21

TECHNICIAN'S PLUGGING REPORT
Operator License # 3711
Operator: Shepler & Thomas, Inc.
Name:
Address P.O. Box 2164
Evergreen, CO 80437-2164

Lease Name Dreitz Well # 3-11
County Seward 195.00
Well Total Depth 6000 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1605

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9 a.m. Day: 21 Month: 11 Year: 1996

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 5999' with 350 sx cement, PBD 5946', Perfs at 5020-28'
1st plug pump 2 sx hulls and 20 sx cement and displace to 4820',
2nd plug pump 50 sx cement and displace to 1630',
3rd plug pump 40 sx cement and displace to 700',
4th plug pump 10 sx cement and displace to 40-0'.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3 p.m. Day: 21 Month: 11 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement and displaced to 4820',
2nd plug pumped 50 sx cement and displaced to 1630',
3rd plug pumped 40 sx cement and displaced to 700',
4th plug pumped 10 sx cement and displaced to 40-0'.

11-27-96

RECEIVED
NOV 27 4 12 07
STATE CORPORATION COMMISSION

Remarks: Used common cement by Sargent's. Recovered 3040' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 05 1996

INV. NO. 47114

XXXXXX observe this plugging.

Signed Gary Winters (TECHNICIAN)

