

1060420

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,809- odo

Center NW/4, SEC. 9 ; T 32 S, R 31 W/E

3960 feet from S section line

3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5293

Lease Name Wessler Well # 1-9

Operator: Helmerich & Payne, Inc.

County Seward 195.00

Name & Address P. O. Box 558

Well Total Depth 6000 feet

Garden City, KS 67846

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1662

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Cheyenne Drilling, Inc. License Number 5382

Address Box 916, Garden City, 67846

Company to plug at: Hour: 10:00 pm Day: 1 Month: December Year: 19 84

Plugging proposal received from Phil Lloyd

(company name) Cheyenne (phone) 316-277-2062

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2980' with 70 sx cement

2nd plug at 1660' with 50 sx cement

3rd plug at 830' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:00 pm Day: 1 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2980' with 70 sx cement, 2nd plug at 1660' with 50 sx

cement, 3rd plug at 830' with 50 sx cement, 4th & 5th plugs - solid bridge - hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with

15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 05 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton CONSERVATION DIVISION
(if additional description is necessary, use BACK of this form.) Wichita, Kansas

INVOICED

DATE 12-20-84

INV. NO. 6068

Signed Paul A. Luthi
(TECHNICIAN)

Paul A. Luthi/Rita J. Lahman