

To: 1 090897  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION 75' W of SE NW NESEC. 8, T 32 S, R 31 W/E  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 175-21,043-0000

2-11

TECHNICIAN'S PLUGGING REPORT

Operator License # 31021  
Operator: Castelli Exploration, Inc.  
Name & Address: 9500 Westgate Dr., Ste. 101  
Oklahoma City, OK 73162

4290 feet from S section line  
1725 feet from E section line

Lease Name Roehr Well # 2-8  
County Seward 187.20  
Well Total Depth 5760 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 1715

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated.

Plugging Contractor Sargent's Casing Pulling Service License Number 6547  
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: Day: 11 Month: 2 Year: 19 98

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

was: 4 1/2" at 5760' w/215 sx cement, PBSD 5702', Perfs at 5504-08, 5567-71'

1st plug pump 25 sx cement and 2 sx hulls on bottom,

2nd plug at 1700' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 p.m. Day: 11 Month: 2 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug pumped 20 sx cement and 200 lbs. hulls on bottom,

2nd plug at 1700' with 50 sx cement,

3rd plug at 600' with 40 sx cement,

4th plug at 40-0' with 10 sx cement. Good circulation.

STATE CORPORATION COMMISSION

FEB 18 1998

Remarks: Used common cement by Sargent's. Recovered 1700' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
I, ~~DATE~~ (did not) observe this plugging.

DATE FEB 18 1998

Signed: [Signature] (TECHNICIAN)

INV. NO. 50095  
2-11 JUN 17 1998