

To: 1 020454
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

4-14 API NUMBER 15-175-21,114-0000 188 R

E/2 NW, SEC. 4, T. 32 S, R. 31 W/E
3960 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4782

Lease Name Quillin Well # 1-4

Operator: Ensign Operating Company
Name & Address 621 17th St., Ste. 1800
Denver, CO 80293

County Seward
Well Total Depth 6000 195.00 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1650

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling Service License Number 6547
Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3 p.m. Day: 10 Month: 4 Year: 19 92

Plugging proposal received from Kirby Lillard
(company name) Sargent's Casing Pulling Service. (phone) 316-624-7455

were: 4 1/2" at 5633' w/325 sx cement, PBTD 5588', Perfs at 5000-5006'
1st plug pump 1 sx hulls and 20 sx cement at perfs, displace with mud,
2nd plug pump 50 sx cement at 1680',
3rd plug pump 30' sx cement at 700',
4th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4:30 p.m. Day: 14 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 20 sx cement at perfs, displaced with mud,

2nd plug pumped 50 sx cement at 1680',
3rd plug pumped 30 sx cement at 700',
4th plug pumped 10 sx cement at 40-0'.
All plugs displaced with mud.

Remarks: Used common cement by Sargent's. Recovered 3117' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
~~1 (copy) observe this plugging.~~
DATE MAY 04 1992
INV. NO. 35120

Signed Glenn R Barlow
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
APR 24 1992
CONSERVATION DIVISION
WICHITA, KS