

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 17520512 - 0000

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5760

OPERATOR: IREX Corp.  
NAME & ADDRESS 1670 Broadway  
Suite 3301  
Denver Colorado  
80202

\_\_\_\_\_ FEET FROM N/S SECTION LINE

\_\_\_\_\_ FEET FROM W/E SECTION LINE

LEASE NAME Hawk WELL # 1

COUNTY Seward

WELL TOTAL DEPTH 6020 <sup>#195.65</sup> FEET

CONDUCTOR PIPE: SIZE \_\_\_\_\_ FEET

SURFACE CASING: SIZE 8 5/8 FEET 1600

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD WELL \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR Reeves + Wilson Inc LICENSE NUMBER 6083

ADDRESS Oklahoma City Oklahoma

COMPANY TO PLUG AT: HOUR: Noon DAY: 5 MONTH: August YEAR: 1987

PLUGGING PROPOSAL RECEIVED FROM Joe Wilson

(COMPANY NAME) Reeves + Wilson (PHONE) \_\_\_\_\_

WERE: Cast Iron Bridge Plug @ 5500 + 2sx cement

ontop, Then fill hole with good mud + spot plugs

1st plug @ 1650' w/50sx, 2nd plug @ 810' w/40sx,

3rd plug @ 40' w/solid Bridge plug + 10sx

cement. Using 60/40 poz mix 2% gel 3% CC

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacey  
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 5:30pm DAY: 5 MONTH: August YEAR: 1987

ACTUAL PLUGGING REPORT Plugged as proposed in above

paragraph

RECEIVED  
STATE CORPORATION COMMISSION  
8-15-1987  
AUG 15 1987  
CONSERVATION DIVISION  
Wichita, Kansas

REMARKS: Mr. Paul Luthi witnessed the plugging.

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacey ✓  
(TECHNICIAN)

INVOICED

DATE 8-17-83  
INV. NO. 5208-W

FORM CP-2/3  
REV. 6-83