

1 020173

8-18-88

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,507-A-0001
S/2 NE SW, SEC. 24, T 32 S, R 31 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 7344
Operator: Clyde M. Becker
Name & Address: 212 First National Bldg.
Ponca City, OK 74601

1650 feet from S section line
3300 feet from E section line
Lease Name Hayden Well # 1
County Seward 195.00
Well Total Depth 6000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1683

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 7:30 a.m. Day: 18 Month: 8 Year: 19 88

Plugging proposal received from Dallas Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2457

were: 4 1/2" at 5786' PBD 5645' Perfs at 5510-14, 5694-98'

1st plug pump 1 sx hulls and 30 sx cement displaced with _____

2nd plug pump 50 sx cement at 1680',

3rd plug pump 25 sx cement at 780',

4th plug pump 10 sx cement at 40-0'.

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1988

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 18 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 30 sx cement to cover perforations,

pressured up, shot off 3100' of 4 1/2", pulled to 1800',

2nd plug ran 15 sx gel at 1850' and 50 sx cement at 1720', did not circulate.

Fluid level 600 in pipe (4 1/2") and 900 in 8 5/8".

3rd plug pulled to 1200' and ran 15 sx gel and circulated gel to top,

4th plug pulled pipe to 800' and pumped 30 sx cement, 5th plug circulated cement from 80-0'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3100' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

(did / x not) observe this plugging.

INVOICED

DATE 8-24-88

INV. NO. 21900

Signed [Signature] (TECHNICIAN)