

2-26

To: 1 051273
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION C W/2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5152

Operator: Lee Banks Oil Company
Name & Address: 200 West Douglas, Suite 550
Wichita, KS 67202

API NUMBER 15-175-20,412-A-0001

4950 feet from S section line
1175 feet from E section line

Lease Name Fieser Well # 1-23
County Seward 167.37

Well Total Depth 5150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1575

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Jerry Dunkin, Inc. License Number 8733

Address P.O. Box 389, Enid, OK 73702

Company to plug at: Hour: 8 a.m. Day: 26 Month: 2 Year: 19 90

Plugging proposal received from Butch Dunkin

(company name) Jerry Dunkin, Inc. (phone) 405-237-6152

were: 4 1/2" at 5148' PBTD 5125' Perfs at 5061-5066'

1st plug pump 2 sx hulls and 25 sx cement to 4950', pump through casing:

2nd plug at 1605' with 50 sx cement,

3rd plug at 760' with 40 sx cement,

4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Mike Wilson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 a.m. Day: 26 Month: 2 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to 4950', Pumped through casing:

2nd plug pumped 50 sx cement at 1605',

3rd plug pumped 40 sx cement at 760',

4th plug pumped 10 sx cement at 40'.

Remarks: Used Class H cement by Dunkin. Recovered 3500' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED
I (did / did not) observe this plugging.

DATE 3-2-90 2-28-90

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 27583
2-26