

1 040578

10-15
API NUMBER 19-175-21,200-0000

87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. C NW SE, SEC. 22, T 32 S, R 31 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30444

Lease Name Hill "A" Well # 1

Operator: Charter Production Company

County Seward 199.87

Name & Address 224 E. Douglas, Suite 400

Well Total Depth 6150 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1637

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SHD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Zenith Drilling License Number 5141

Address 505 4th Financial Ctr., Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 14 Month: 10 Year: 19 91

Plugging proposal received from Greg

(company name) Zenith Drilling (phone) 316-265-6697

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 3000' with 100 sx cement, 2nd plug at 1660' with 50 sx cement,

3rd plug at 600' with 50 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 2 a.m. Day: 15 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 3000' with 100 sx cement,

2nd plug at 1660' with 50 sx cement,

3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 17 1991
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

INVOICED

DATE 10-29-91

INV. NO. 33542

10-15

EFFECTIVE DATE: 9-14-91

State of Kansas 15-175-21,200-0000
NOTICE OF INTENTION TO DRILL

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

DISTRICT # 1
SEA? Yes X No

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date October 1, 1991 app Spot C NW SE Sec 22 Twp 32 S. Rg 31 East West

OPERATOR: License # 30444
Name: Charter Production Company
Address: 224 E. Douglas, Suite 400
City/State/Zip: Wichita, KS 67202
Contact Person: Robert C. Spurlock
Phone: 3160264-2808

CONTRACTOR: License # 5141
Name: Zenith Drilling

Well Drilled For: Well Class: Type Equipment:
X Oil ... Enh Rec ... Infield X Mud Rotary
Gas ... Storage ... Pool Ext. ... Air Rotary
OWVO ... Disposal X Wildcat
Seismic: ... # of Holes ... Other
Other

if OWVO: old well information as follows:
Operator: OCT 17 1991
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location: Wichita, Kansas

Proprated + Spaced on Maturation Formation AFFIDAVIT Exp. 3/9/92 550' Alt. I Req.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

5.12
Didn't call in Spud

Pusher Greg
SPUD DATE 10-1-91 INIT.
LENGTH SURFACE PLANNED
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2" @ 16.37' CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 6150 FORMATION St. Louis.
RAN PIPE @ DV TOOL ALT II DONE
SX SX Y N
Arbuckle Plug @ Ft. W/ SX
1 Hug./Council @ 3000 Ft. W/ 100 SX
2 Anhydrite Base @ 1660 Ft. W/ 50 SX
3 1/2 Base Anyh. @ 600 Ft. W/ 50 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
4 40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond
Hauling
TECHNICIAN S.P. DATE 10-14-91
TYPE OF CEMENT 60/40 002 6 40
STARTING TIME 10:00 (AM/PM) DATE 10-14-91
COMPLETION TIME 2:00 (AM/PM) DATE 10-15-91
CEMENT COMPANY Halliburton