

1 020224

4-14

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-21,088 - 0000

SE SW, SEC. 21, T 32 S, R 31 W/E

660 feet from S section line

3300 feet from E section line

Lease Name Siemens/Hospital Foundation #1-21 Well #

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

County Seward 195.00

Operator: Shepler & Thomas, Inc.

Name & Address P.O. Box 1162

Well Total Depth 6000 feet

Liberal, KS 67905-1162

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1594

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Beredco License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 14 Month: 4 Year: 19 89

Plugging proposal received from Frank Buebe

(company name) Shepler & Thomas, Inc. (phone) 316-624-0750

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2850' with 80 sx cement, 2nd plug at 1620' with 50 sx cement,

3rd plug at 600' with 30 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Blenn Barlow

(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 a.m. Day: 14 Month: 4 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 2850' with 80 sx cement,

2nd plug at 1620' with 50 sx cement,

3rd plug at 600' with 30 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

RECEIVED STATE CORPORATION COMMISSION

APR 17 1989

CONSERVATION DIVISION Wichita, Kansas

INVOICED (do not) observe this plugging.

Signed Blenn Barlow (TECHNICIAN)

DATE 4-24-89

INV. NO. 24456