

To: 1 051549 4-29  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-20,206-0000 247R  
C S/2 SE, SEC. 34, T. 32 S, R 31 W/E  
660 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 4058  
Operator: American Warrior Inc.  
Name & Address: P.O. Box 399  
Garden City, KS 67846

Lease Name Singley Well # A-1  
County Seward  
Well Total Depth 3220 104.65 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 620

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Halliburton Services License Number \_\_\_\_\_  
Address P.O. Box 1568, Liberal, KS 67905

Company to plug at: Hour: 1 p.m. Day: 29 Month: 4 Year: 19 92

Plugging proposal received from Frank Boswell

(company name) American Warrior Inc. (phone) 316-624-7700

were: 4 1/2" at 3220' w/180 sx cement, Perfs at 3028-84', TOC 2250'  
Perfs have been squeezed, sanded in to 1770', Glorietta broke in at 1770'  
1st plug circulate 3 sx hulls and 150 sx cement,  
2nd plug pump 250 sx cement down 8 5/8" X 4 1/2" annulus.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:40 p.m. Day: 29 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped 125 sx cement down 8 5/8" X 4 1/2" annulus, cement circulated up the 4 1/2",  
2nd plug pumped down 4 1/2" casing with 3 sx hulls and 275 sx cement.  
Maximum pressure 1000 psi and shut in 700 psi.

Remarks: Used 60/40 Pozmix 6% gel 3% cc by Halliburton. No casing recovery.

(If additional description is necessary, use BACK of this form)  
I (did / ~~did not~~) observe this plugging.

DATE 5-14-92  
INV. NO. 35232

Signed Richard W. Lacey (TECHNICIAN)

RECEIVED  
MAY 1 1992  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

# Rosel

WELL PERFORATORS, INC.

# SONIC BOND LOG

COMPANY INVESTORS DRILLING &  
EXPLORATION COMPANY INC.

WELL SINGLEY A #1 WELL FILE

FIELD MASSON

COUNTY SEWARD STATE KANSAS

Location:

Sec. 34 - 32S - 31W  
Approx. C 1/2 SE

Other Services:

G/R-N

Permanent Datum: \_\_\_\_\_ Elev. 2770  
Log measured from G.L. ft above perm. datum  
Drilling measured from \_\_\_\_\_

Elev.: K.B. \_\_\_\_\_  
D.F. \_\_\_\_\_  
G.L. 2770

Date	<u>8-14-73</u>
Run No.	<u>ONE</u>
Type Log	<u>BOND</u>
Depth—Driller	
Depth—Logger	<u>3170</u>
Bottom logged interval	<u>2100</u>
Top logged interval	
Type fluid in hole	<u>WATER</u>
Level	<u>FULL</u>
Type Cement	
Cement Top	
Max. rec. temp., deg F.	
Operating rig time	<u>2 HRS</u>
Recorded by	<u>JOHNSON &amp; VOOR</u>
Witnessed by	<u>MR. Mc KEEN</u>

BORE-HOLE RECORD				CASING RECORD			
RUN No.	Bit	From	To	Size	Wgt.	From	To
				<u>4 1/2</u>		<u>SURT</u>	<u>3170</u>

This Heading and Log conforms to API RP 38 A

Fold Here

Joan Finney  
Governor

Jim Robinson  
Chairman

F. S. Jack Alexander  
Commissioner

Rachel C. Lipman  
Commissioner

Judith McConnell  
Executive Director

Brian Moline  
General Counsel



# Kansas Corporation Commission

## NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

April 30, 1992

American Warrior Inc  
Box 399  
Garden City KS 67846

Singley 4-1  
API 15-175-20,206  
C S2 SE  
Sec. 34-32-31W  
Seward County

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). Failure to do so is punishable by an administrative penalty of up to \$1000. If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in dark ink, appearing to read "David P. Williams".

David P. Williams  
Production Supervisor

Conservation Division  
William R. Bryson  
Director  
200 Colorado Derby Bldg.  
202 W. 1st Street  
Wichita, Kansas 67202-1286  
Telephone (316) 263-3238

District: #1 304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760