

1 020284

1-9

147

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-175-21,019-0000

SW SE, SEC. 33, T 32 S, R 31 W/E  
660 feet from S section line  
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Lease Name Kulp Well # 1-33

Operator: Shepler & Thomas, Inc.

County Seward 195.00

Name & Address P.O. Box 2164

Well Total Depth 6000 feet

Evergreen, CO 80439

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1599

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 3 p.m. Day: 8 Month: 1 Year: 19 90

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 6000' PBD 5988' Perfs at 5923-26, 5941-51' TOC 4250'

1st plug pump 2 sx hulls and 50 sx cement,

2nd plug pump 50 sx cement at 1650',

3rd plug pump 35 sx cement at 625',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 5:30 p.m. Day: 9 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perfs, displaced with mud between all plugs,

2nd plug pumped 50 sx cement at 1650-1450',

3rd plug pumped 35 sx cement at 700' to 560',

4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 4123' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED

(d d XXXXX) observe this plugging.

DATE 1-29-90

Signed Glenn R. Barlow (TECHNICIAN)

INV. NO. 27231

RECEIVED STATE CORPORATION COMMISSION JAN 18 1990 1-18-90 CONSERVATION DIVISION