

To: 1020283
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 3711

Operator: Shepler & Thomas, Inc.

Name &

Address P.O. Box 2164

Evergreen, CO 80439

Abandoned Oil Well _____ Gas Well ☒ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pullers License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 1 p.m. Day: 6 Month: 1 Year: 19 90

Plugging proposal received from Kirby Lillard

(company name) Sargent's Casing Pullers (phone) 316-624-7455

were: 4 1/2" at 5764' PBTD 5075' Perfs at 5002-14'

1st plug pump 1 sx hulls and 25 sx cement to bottom,

2nd plug pump 50 sx cement at 1700',

3rd plug pump 35 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part ☒ None _____

Operations Completed: Hour: 11:30 a.m. Day: 8 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement at perforations displaced with mud,

2nd plug pumped 50 sx cement at 1700' to 1500' displaced with mud,

3rd plug pumped 35 sx cement at 700-560',

4th plug pumped 10 sx cement at 40-0'.

Remarks: Used common cement by Sargent's. Recovered 3208' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(could / should) observe this plugging.

DATE 1-29-90

INV. NO. 27230

Signed

(TECHNICIAN)