

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colcrado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89
RECEIVED
KANSAS CORPORATION COMMISSION

MAY 06 1993

WELL PLUGGING APPLICATION FORM
(File One Copy)

CONSERVATION DIVISION
WICHITA, KS

API NUMBER 15-119-10137-0000 (of this well).

(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Phillips Petroleum Company OPERATOR'S LICENSE NO. 5229 ^{6/93}

ADDRESS Box 358, Borger, TX 79008-0358 PHONE # (806) 275-3383

LEASE (FARM) Herman A WELL NO. 1 WELL LOCATION NW/4 NW/4 COUNTY Meade

SEC. 33 TWP. 32S RGE. 30 ~~(E) (W)~~ TOTAL DEPTH 5720 PLUG BACK TD 5668

Check One:

OIL WELL GAS WELL D & A SWD or INJ WELL DOCKET NO. _____

SURFACE CASING SIZE 8 5/8" SET AT 1804' CEMENTED WITH 975 SACKS

CASING SIZE 5 1/2" SET AT 5700 CEMENTED WITH 75 SACKS

PERFORATED AT Morrow-Keys Sand 5574'-5590'

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Plug 1) CIBP @ 5524' w/2 1/2 sx cmt on top, Plug 2) 75 sx cmt

1854'-1754' (will be tagged), Plug 3) 40 sx cmt 1150'-1050', Plug 4) 40 sx cmt 700'-600', and

Plug 5) 10 sx cmt 40'-surface. Recover 5 1/2" csg @ 2000'. Weld on ID plate w/needle valve.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not explain.)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN upon approval

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Ed Williamson PHONE # (806) 898-0445

ADDRESS c/o Kevin Hoff Box 358, Borger, TX 79008-0358

PLUGGING CONTRACTOR Phillips Petroleum Co. LICENSE NO. 5229 ^{6/93}

ADDRESS Box 358, Borger, TX 79008-0358 PHONE # (806) 275-3411

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: G.D. Gillham
(Operator or Agent) Dir. Res. Engr.

DATE: 4-5-93

Joan Finney
Governor

Jim Robinson
Chairman

F. S. Jack Alexander
Commissioner

Rachel C. Lipman
Commissioner

Judith McConnell
Executive Director

Brian Moline
General Counsel



Kansas Corporation Commission

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

May 6, 1993

Phillips Petroleum Company
P O Box 358
Borger TX 79008-0358

Herman A #1
API 15-119-10137
NW/4 NW/4
SEC. 33-32S-30W
Meade County

Dear Mr. Ed Williamson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams
Production Supervisor

Conservation Division
William R. Bryson
Director
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, Kansas 67202-1286
Telephone (316) 263-3238

District: #1 304 W. McArtor
Dodge City KS 67801
(316) 225-6760