


WELL PLUGGING RECORD

Give All Information Completely
Take Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

PRATT County. Sec. 28 Twp. 28S Rge. (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines C SE NE
Lease Owner Arnell
Lease Name Dudrey "A" Well No. 1
Office Address 533 Petroleum Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 24 19 59
Application for plugging filed July 24 19 59
Application for plugging approved July 24 19 59
Plugging commenced July 25 19 59
Plugging completed July 25 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production -- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp
Producing formation -- Depth to top -- Bottom -- Total Depth of Well 4490 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	358	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from -- feet to -- feet for each plug set.

Filled hole from Total Depth, 4490, to 300 ft. with mud.
Cement plug 300 to 234' with 20 sacks cement. Mud
234 to 35'. Cement plug 35 to 10'. Heavy rotary mud 10'
to cellar.

STATE CORPORATION COMMISSION
AUG 3 1959 08-03-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor National Drilling Company, Inc.
Address 535 Petroleum Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.
Howard A. Stoskopf (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Howard A. Stoskopf
535 Petroleum Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 31 day of July, 1959
RUBY GOURLEY
My commission expires July 13, 1960
Notary Public.

PLUGGING
FILE SEC 28 T 28 R 11W
BOOK PAGE 57 LINE 26

DRILLERS LOG

Dudrey "A" #1

CASING RECORD: 8 5/8" @ 355
w/225 sx Sunset

COMPANY: National Drilling Company, Inc.
CONTRACTOR: National Drilling Company, Inc.

DESCRIPTION: C SE NE
28-28S-11W
Pratt County
Kansas

COMMENCED: July 14, 1959
COMPLETED: July 25, 1959

ELEVATION: 1805 KB
1803 DF

TOTAL DEPTH: 4490 (-2685)

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Clay	0	235	
Sand & Redbed	235	355	
Shale & Shells	355	1025	
Shale & Lime	1025	1695	
Lime & Shale	1695	2080	
Lime	2080	2460	
Shale & Shells	2460	2690	
Shale & Lime	2690	3070	
Shale & Shells	3070	3260	
Shale & Lime	3260	3412	
Lime & Shale	3412	3535	
Lime	3535	4184	
Shale & Lime	4184	4360	
Lime	4360	4430	
Lime & Shale	4430	4475	
Shale & Sand	4475	4490	

STAMP: AUG 3 1959
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

NATIONAL DRILLING COMPANY, INC.

Howard A. Stoskopf
Howard A. Stoskopf

Subscribed and sworn to before me this 31st day of July, 1959

Ruby Sourley
Notary Public

PLUGGING
FILE SEC 2PT 28S-11W
BOOK PAGE 57 LINE 26