

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

API NUMBER #15-151-20,848

LEASE NAME Willinger

WELL NUMBER #3

         Ft. from S Section Line

         Ft. from E Section Line  
 C SW/4 SW/4

SEC. 28 TWP. 28S RGE. 11WE or (NW)

COUNTY Pratt

Date Well Completed         

Plugging Commenced 7-15-88

Plugging Completed 8-18-88

LEASE OPERATOR Raymond Oil Co., Inc.

ADDRESS P.O. Box 48788  
 Wichita, Kansas 67201

PHONE (316) 267-4214 OPERATORS LICENSE NO. 5046

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed?          If not, is well log attached?         

Producing Formation          Depth to Top          Bottom          T.D. 2700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	From	To	Size	Put In	Pulled out
			8-5/8"	236'	none
			4-1/2"	2699'	2003'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from          feet to          feet each set.

Plugged off bottom with sand to 2560' and 4 sacks cement. Ran shot to 2003', pulled a total of 50 joints of 4-1/2" casing. Plugged surface with 3 hulls, 10 gel, 50 cement, 10 gel, 1 hull, 100 sacks cement, 60/40 pos., 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso  
 Box 347  
 (Address) Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 22nd day of August, 19 88

Irene Hoover  
 Notary Public

My Commission Expires:         

