


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

PRATT County, Sec. 27 Twp. 28 Rge. (E) 11 (W)
Location as "NE/CNWSW4" or footage from lines NW NW NE
Lease Owner SANTA FE PIPE & SUPPLY
Lease Name ROSE Well No. 1
Office Address P. O. BOX 562 - GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed FEBRUARY 25 19 55
Application for plugging filed DECEMBER 24 19 62
Application for plugging approved DECEMBER 28 19 62
Plugging commenced JANUARY 16 19 63
Plugging completed JANUARY 25 19 63
Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ARCHIE ELVING
Producing formation Depth to top Bottom Total Depth of Well 4595' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	310'	NONE
				5 1/2"		1887'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4370' - 4330' FILLED WITH SAND
4330' - 4300' 5 SACKS CEMENT
4300' - 210' MUD
210' - 200' ROCK BRIDGE
200' - 140' 20 SACKS CEMENT
140' - 40' MUD
40' - BASE 10 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1963
02-27-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GLENN & SMITH PIPE PULLING COMPANY
Address P. O. BOX 114 - ELLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T. L. NUTT (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
P. O. BOX 562 - GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 25TH day of FEBRUARY 19 63

My commission expires JULY 31, 1966

[Signature]
Notary Public.

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

COPY


Company- TRANS ERA PETROLEUM, INC.
Farm- Roso No. 1

SEC. 27 T. 28 R. 11W
NW NW NE

Total Depth. 4595'
Comm. 2-5-55
Shot or Treated.
Contractor.
Issued. 4-2-55

Comp. 2-25-55

County Pratt KANSAS



CASINO:
8 5/8" 310' cem w/230 sx

Elevation. 1775'

Production: Dry

Figures indicate Bottom of Formations

sand	95
shale-shells	180
red bed	580
shale-shells	1365
salt	1440
anhydrite	1470
shale-shells	1575
lime-shale	1690
lime	1926
lime-shale	1985
lime	2110
lime-chert	2142
Mississippi lime	2150
shale (Kinderhook)	2157
shale-lime	2185
shale	2317
lime-chert	2333
lime	2399
shale-sand	2415
shale	2425
shale-sand	2460
sand	2470
shale-sand	2515
shale	2543
Arbuckle	2560
lime	2595
Total Depth	

Tops: Scout	
Hochspr	2474
Toronto	2489
Douglas	2505
Brown Linc	2628
Lansing	2668
Mississippi	2726
Kinderhook	2757
Viola	2817
Dolomite	2827
Simpson Sand	2852
Arbuckle	2843

RECEIVED
STATE CORPORATION

FEB. 27 1963

CONSERVATION DEPT.
Wichita, Kansas

RECEIVED

DEC 29 1962

Santa Fe Pipe & Supply