

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Pratt County. Sec. 34 Twp. 28 Rge. 11 (E) W (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines SW SW NE 1/4

Lease Owner M. B. Arner

Lease Name Wagner Well No. 1

Office Address 710 Petroleum Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry

Date well completed Aug. 16, 19 52

Application for plugging filed " " 19 52

Application for plugging approved " " 19 52

Plugging commenced " " 19 52

Plugging completed " " 19 52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation Depth to top Bottom Total Depth of Well 4625 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	299	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy Rotary mud to 299 ft.
set plug and ran 20 sacks cement through drill
pipe. Mudded hole to 35 ft. set plug and 10
sacks cement to surface.

RECEIVED
STATE CORPORATION COMMISSION
AUG 20 1952
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor M. B. Arner
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. C. Sponenberg (employee of owner) or owner or operator of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of August, 1952

My commission expires Sept. 17, 1955.

PLUGGING
FILE SEC 34 T 28 R 10
BOOK PAGE 38 LINE 14

Notary Public.

LOG

Company: M. B. Armer & North
American Car Corporation
Contractor: W. D. Armer (Unit Rig)
Drilling Commenced: 7/31/52
Drilling Completed: 8/16/52
Elevations: 1811 K.B.
1808 D.F.

Farm: Wagner #1
Location: SW SW NE Sec. 34-20S-11W
Pratt County, Kansas
Casing Record: 8-5/8" casing at 299'
with 200 sacks cement.

(figures below indicate bottoms)

Surface soil & Sand	80
Sand	185
Red Bed & Shale	800
Shale & Shells	950
Anhydrite & Shale	1100
Shale, Shells & Salt	1365
Shale & Salt	1650
Shale & Lime	1955
Shale & Lime Breaks	2115
Shale & Lime	3823
Lime	3860
Shale & Lime	4055
Lime	4150
Shale & Lime	4197
Lime	4295
Shale & Lime	4415
Cherty Lime & Shale	4444
Shale & Lime	4515
Shale Chert & Sand	4544
Sandy Lime	4583
Lime	4625
R.T.D.	4625

FORMATION TOPS (R.B. Meas.)

Lansing - Kansas City	3707
Conglomerate	4205
Viola	4398
Simpson	4487
Arbuckle	4585

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

RECEIVED M. B. ARMER
STATE CORPORATION COMMISSION
AUG 20 1952

CONSERVATION DIVISION
Wichita, Kansas

BY Merle Britting

STATE OF KANSAS
COUNTY OF SEDWICK

Subscribed and sworn to before me, a notary public, in and for said County and State this 18th day of August, 1952.

PLUGGING
FILE SEC 34-28R-14
BOOK PAGE 38 LINE 14

Walter Walton
Notary Public