


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pratt County. Sec. 34 Twp. 28S Rge. 11 (E) 11 (W)
Location as "NE/CNW/SW" or footage from lines. SW NE SW
Lease Owner Roger F. Williams Company
Lease Name Dudrey Well No. 1
Office Address 11 1/2 East Main, Chanute, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 26 19 67
Application for plugging filed October 26 19 67
Application for plugging approved October 26 19 67
Plugging commenced October 26 19 67
Plugging completed October 26 19 67
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4540 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	330'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged as follows: Plugged at 250' with 2 sacks of dry cement, 23 sacks of cement and 1/2 sack of hulls and mud to 40'; plugged at 40' with 1 sack of dry cement, 10 sacks of cement and 1/2 sack of hulls. Two sacks of cement in rat hole and 2 sacks of cement in mouse hole. Plug down at 6:30 A. M. October 26, 1967.

FILED
OCT 31 1967 10-31-67
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Charles W. Steincamp (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of October, 1967
Elaine H. Taylor
Elaine H. Taylor Notary Public.

My commission expires December 14, 1969

D R I L L E R S L O G

#1 Dudrey

CASING RECORD: Ran 330.84' of new 8-5/8" surface casing.	COMPANY: Roger F. Williams Company	DESCRIPTION: SW NE SW Section 34-28S-11W Pratt County, Kansas
TOTAL DEPTH: 4540'	CONTRACTOR: STRATA DRILLING, INC.	ELEVATION: 1812' KB
	COMMENCED: October 10, 1967	
	COMPLETED: October 26, 1967	

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Clay & Sand	0	135	Ran 330.84' of new 8-5/8" surface casing; set and cemented at 330' with 250 sacks of cement. Plug down at 9:45 A. M. October 11, 1967.
Red Bed & Shale	135	775	
Shale & Shells	775	1896	
Shale & Lime	1896	2381	
Shale	2381	2670	
Shale & Lime	2670	2850	
Lime	2850	2966	
Shale & Lime	2966	3271	
Lime	3271	3842	
Cherty Lime	3842	3875	
Lime	3875	4016	
Lime & Shale	4016	4085	
Lime	4085	4212	
Cherty Lime & Shale	4212	4273	
Lime	4273	4540	

RECEIVED
 STATE OF KANSAS COMMISSIONER OF
 GEOLOGICAL SURVEY
 OCT 31 1967
 10-31-1967
 GENEALOGY DIVISION
 WASHINGTON, MISSOURI

Total Depth 4540'

D. & A.

Plugged hole as follows: Plugged at 250' with 2 sacks of dry cement, 23 sacks of cement and $\frac{1}{2}$ sack of hulls and mud to 40'; plugged at 40' with 1 sack of dry cement, 10 sacks of cement and $\frac{1}{2}$ sack of hulls. Two sacks of cement in rat hole and 2 sacks of cement in mouse hole. Plug down at 6:30 A. M. October 26, 1967.


STATE OF KANSAS)
) ss.
 COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.


 Charles W. Steincamp, President

Subscribed and sworn to before me this 27th day of October, 1967.


 Elaine H. Taylor, Notary Public

My Commission Expires:

December 14, 1969