

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pratt SEC. 33 TWP. 28 RGE. 11W E/W
Location as in quarters or footage from lines:
100' S of C NE NE

Lease Owner Raymond Oil Co., Inc.
Lease Name Ford #1 Well No. _____
Office Address One Main Place Suite 900 Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 8-25-82
Plugging completed 9-9-82
Reason for abandonment of well or producing formation Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. METZ
Producing formation _____ Depth to top _____ bottom _____ T.D. 2720'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	254'	none
				4-1/2"	2720'	2084'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged off bottom with sand to 2530' and ran 4 sacks cement. Shot casing @2530' and pulled a total of 53 joints of 4-1/2" casing. Plugged well with 3 sacks hulls, 25 sacks gel, 1 sack hulls, released plug and displaced with 125 sacks cement.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of September, 1982

My Commission expires: 


STATE CORPORATION COMMISSION
RECEIVED
Notary Public
SEP 14 1982
CONSERVATION DIVISION
Wichita, Kansas

WELL LOG

COMPANY Raymond Oil Company

SEC. 33 T. 28S R. 11W

FARM Ford No. 1

NO. 1

LOC. NW-SE NENE


TOTAL DEPTH 2720'

COUNTY Pratt

DATE 12-16-77

DATE 12-21-77

CONTRACTOR DaMac Drilling Inc.



CASING

8 5/8" set @ 254

ELEVATION

PRODUCTION 4 1/2" set @ 2720

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	0	145
RedBed	145	255
RedBed, Shale	255	815
Shale	815	1700
Lime, Shale	1700	2720 RTD

RECEIVED
STATE CORPORATION COMMISSION
JUN - 7 1982
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Barton } 88

I, Martha J. McKown of DaMac Drilling Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the Ford No. 1 well.

Martha J. McKown

Subscribed and sworn to before me this 28th day of December 19 77

My Commission Expires: 4-28-81

Lana L. Remmert
NOTARY PUBLIC

LANA L. REMMERT
Barton County, Kansas
My Appl. Exp. 4-28-81

XC: MRS