

15-119-10248-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 12-29-66

LEASE NAME Adams #1

WELLS NUMBER #1

1000 Ft. from S Section Line

1000 Ft. from E Section Line

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

rec'd 6-19-98

RECEIVED
KANSAS CORP. COMM.

LEASE OPERATOR Quinque Operating Company

SEC. 4 TWP. 35 SRGE. 30 (E) or (W)

ADDRESS P. O. Box 2738 Liberal, KS 67905-2738

COUNTY Meade

PHONE (316) 624-2578 OPERATORS LICENSE NO. 5225

Date Well Completed 12-29-66

Character of Well Oil

Plugging Commenced 6-9-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-10-98

The plugging proposal was approved on 3/18/98 (date)

by Dodge City, Kansas (KCC District Agent's Name).

Is ACO-1 filed? If not, is well log attached? OLD WELL - Drilled by Wm. Gruenerwald

& Associates 12-29-66

Producing Formation Depth to Top Bottom T.D. 6300

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				2-7/8"	6296	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.
Ran slickline in 2-7/8" - found solid bridge in 2-7/8" @ 1518'

Pumped via 2-7/8" 50 bbls plugging mud pumped 60 sks cement POOH to approx 600'

Pumped 60 saks cement to 60' Mixed & pumped 15 saks cement to surface

Plug placement as follows - 1250' to 1080', 600' to 430', 60' to 03' as per Scott Alberg

of KCC District #1 - witnessed & approved by Gary Winter of KCC

Cut off and capped 8-8/8" casing

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6254

Address P. O. Box 506 Liberal, KS 67905-0506

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Michael Moore - Quinque Operating Company

STATE OF Kansas COUNTY OF Seward, ss.

Michael Moore


(Employee or Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Michael Moore

(Address) Michael Moore, President
P. O. Box 2738 Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 18 day of June, 19 98



Beverly A. Stahle
Beverly A. Stahle Notary Public
My Commission Expires: 11-27-99

WELL LOG

COMPANY Wm Gruenerwald and Associates, Incorporated

SEC. 4 T. 35S R. 30W

FARM Adams NO. 1


LOC. 150' NE of C SE NE

TOTAL DEPTH 6340'

COUNTY Meade

COMM. 12-1-66 COMP. 12-18-66

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 1361' w/800 sx

2 7/8" @ 6329' w/300 sx

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 467' Sand, Clay and Red Bed
- 1361' Red Bed, Sand and Anhydrite
- 1815' Shale and Shells
- 2524' Shale and Lime
- 3452' Lime and Shale
- 3648' Lime and Chalk
- 4110' Lime and Shale
- 4380' Shale and Lime
- 4647' Lime and Shale
- 4679' Lime
- 4834' Lime and Shale
- 5100' Lime
- 5158' Lime and Shale
- 6340' Lime
- 6340' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 FEB 14 1967
 CONSERVATION DIVISION
 Wichita, Kansas

State of Kansas }
 County of Barton } ss

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Adams No. 1 well.

Sam N. Stephens

Subscribed and sworn to before me this 23rd day of December 19 66

My Commission Expires: November 5th, 1969

Richard D. Boys
 NOTARY PUBLIC