

031523

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 063-20,329-00-00
C NE NE SE, SEC. 18, T 14 S, R 28 W/EX

2310 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 03122

Lease Name Smith H Well # 1

Operator: Vintage Pet. Inc.

County Gove

Name: Address 4200 One William Center

Well Total Depth 4470 feet

Tulsa, OK. 74172

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 359

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Cheyenne Well Service License Number 6454

Address Ness City, Ks.

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Gary Rowe

(company name) Vintage (phone)

logs: 8 5/8 set at 359 w/225 sks. 4 1/2 set at 4470 w/150 sks. PSTD

4365. Perf 4218 - 28. Holes in casing. Packer struck at 3896 w/fish at

3802. Shot at 1186 - 1900., Order 200 sks 60/40 poz 2% gel 2% cc.

350 sks 60/40 poz 8% gel 500 lbs. hulls. Halliburton Cement Co.

Company water, Hensley water. Cheyenne Well Service rig.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: Day: 4 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Ran in w/rfts packer and set at 3300. Pumped

200 sks cement blend to max psi 1000 lbs. Below packer, across perfs,

Retrieved rfts, open end tubing to 3270. Stage cement blend from

3300 to surf. Tied onto 4 1/2 and sq w/total of 500 sks w/ 300 lbs.

Close psi 200 lbs. Sq 8 5/8 w/100 sks cement blend to max psi

300 lbs. Close in psi 150 lbs. Plug completed.

Remarks: (If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

G. S.

Signed *Carl Goodrow* (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
FEB 14 2007
WICHITA, KS
CONSERVATION DIVISION