

To: 1 040252
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-21 216
API NUMBER 15- 151-20,953-00-00
SW SW SW, SEC. 17, T 27 S, R 15 W/EX

TECHNICIAN'S PLUGGING REPORT
Operator License # 5364
Operator: Beren Corporation
Name: Box 723
Address: Hays, KS 67601

330 feet from S section line
4950 feet from E section line
Lease Name Pauline Well # 1
County Pratt 150.05
Well Total Depth 4617 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11 a.m. Day: 21 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4616' PBD 4580' Perfs at 4530-40'
1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
03-28-89
MAR 28 1989

Plugging Proposal Received by James R. Kapp
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completion Hour: 11:45 a.m. Day: 21 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4480' and dumped 4 sx cement on top of
sand bridge with bailer,
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.
Maximum pressure 550 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 2500' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE 3-30-89
INV. NO. 24292

Signed Stephen J. Pfeiffer
(TECHNICIAN)