

3-21 217
API NUMBER 15- 151-21,046-00-00

To: 1 040251
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

E/2 E/2 SE, SEC. 17, T 27 S, R 15 W/4E

TECHNICIAN'S PLUGGING REPORT
Operator License # 5364
Operator: Beren Corporation
Name & Address: Box 723
Hays, KS 67601

1320 feet from S section line
330 feet from E section line
Lease Name Pauline A Well # 1
County Pratt 149.34
Well Total Depth 4595 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 414

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 1:15 p.m. Day: 21 Month: 3 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4595' PBD 4565' Perfs at 4466-70'

1st plug sand back to 4410' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
03-28-89
MAR 28 1989

Plugging Proposal Received by James R. Kapp (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations ~~at~~ ~~the~~ ~~well~~: Hour: 2 p.m. Day: 21 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4400' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 2500' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE 3-30-89

INV. NO. 24291

Signed Stephen J. Pfeifer (TECHNICIAN)