

To: 1 040652 4-27
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,006-00-00
S/2 SW, SEC. 16, T. 27 S, R 15 W/R
530 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7118
Operator: Seagull Operating Inc.
Name & Address 416 Travis, Suite 1215
Shreveport, LA 71101

Lease Name Lippleman Well # 1
County Pratt 151.12
Well Total Depth 4650 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 474

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 1 p.m. Day: 27 Month: 4 Year: 19 92

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 4648' w/175 sx cement, PBTD 4615', Perfs at 4484-88'

1st plug sand back to 4434' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 27 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4434' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 250 psi and shut in 250 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3090' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

DATE 5-6-92

WV, NO. 35174

Signed Stephen J. [Signature]
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
MAY 1 1992
CONSERVATION DIVISION
WICHITA, KANSAS