

1 030325

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SW SW SW, SEC. 15, T 27 S, R 15 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,236-00-00

TECHNICIAN'S PLUGGING REPORT

660 feet from S section line

4620 feet from E section line

Operator License # 5087

Lease Name Newby Well # 2-15

Operator: Texas Energies, Inc.

County Pratt

Name & Address P. O. Box 947

Well Total Depth 4640 150.80 feet

Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 8 Month: November Year: 19 84

Plugging proposal received from Joe Maze

(company name) Kelso (phone) 316-938-2475

were: 4 1/2" set at 4638' PBD 4592' Perfs 4528-4529.5

1st plug sand back to 4480' and dump 4 sx cement on top of sand through bailer.

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 08 1984
11-08-84

Plugging Proposal Received by Steve Blumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 8 Month: November Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4638' PBD 4592' Perfs 4528-4529.5'

1st plug sanded back to 4480' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pumped an additional 125 sx cement.

Maximum pressure 300 psi and shut in pressure 0

Remarks: Recovered 2507' of 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

(did not observe this plugging.)

DATE 11-19-84

Signed Steve Blumont
(TECHNICIAN)

INV. NO. 4815