

1050467

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,573 -00-00

SW SW NE, SEC. 5, T 28 S, R 12 W/R
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5313

Lease Name Barker "C" Well # 1

Operator: F & M Oil Co., Inc.

County Pratt 147.23

Name & Address 422 Union Center

Well Total Depth 4530 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 13" feet 280

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Union Drilling Co., Inc. License Number 5103

Address 422 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 8:00 pm Day: 28 Month: February Year: 19 85

Plugging proposal received from T. F. Brown

(company name) Union (phone) 316-262-1872

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement

2nd plug at 330' with 40 sx cement

3rd plug solid bridge hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 10 sx cement, 6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:30 pm Day: 28 Month: February Year: 1985

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement, 2nd plug at 300' with 40

sx cement, 3rd & 4th plugs - solid bridge- hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 10 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 11 1985

03-11-85

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton

(If additional description is necessary, use BACK of this form.)

~~XXXX~~, did not observe this plugging.

DATE 3-12-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 7305