

7-18

To: 1 040300
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,148-40-30

SE NE SE, SEC. 3, T 28 S, R 12 W/E

1650 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

Lease Name Hissons Well # 1

Operator: Falcon Exploration, Inc.

County Pratt 135.85

Name & Address 125 North Market, Suite 1075

Well Total Depth 4180 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 273

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 10:30 a.m. Day: 18 Month: 7 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-792-6970

were: 4 1/2" at 4177' PBTB 4132' Perfs at 4081-84, 4025-29, 3990-94, 3954-58'

1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 130 sx cement.

Plugging Proposal Received by Mike Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 18 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on sand bridge with bailer.

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls and 130 sx cement. Pumped through 2" collar welded in 10 3/4".

Maximum pressure 300 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2109' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.) Kansas

JUN 31 1989 07-31-89

INVOICED

DATE 8-1-89

INV. NO. 25472

Signed Stephen J. Pfeiffer
(TECHNICIAN)