

7-18

To: 040301  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,181-00-00  
W/2 NW SW, SEC. 2, T 28 S, R 12 W/E

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5316

1980 feet from S section line  
4950 feet from E section line  
Lease Name Hissons Well # 2

Operator: Falcon Exploration Inc.  
Name & Address 125 North Market, Suite 1075  
Wichita, KS 67202

County Pratt 147.88  
Well Total Depth 4550 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 10 3/4 feet 279

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:45 a.m. Day: 18 Month: 7 Year: 19 89

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-792-6970

were: 4 1/2" at 4168' PBD 4151' Perfs at 3965-68, 4001-04, 4058-60'

1st plug sand back to 3915' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 130 sx cement.

Plugging Proposal Received by Mike Wilson  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 18 Month: 7 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 3915' and dumped 4 sx cement on top of  
sand bridge with bailer,

2nd plug pumped down 10 3/4" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 100 lbs. hulls, released 10 3/4" wiper plug and pumped 130 sx cement.

Maximum pressure 350 psi and shut in 150 psi.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 31 1989 7-31-89

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2097' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

**INVOLVED**  
I (and ~~others~~) observe this plugging.

DATE 8-1-89

Signed Stephen J. Pfeifer  
(TECHNICIAN)

WV. NO. 25473