

10-20

To: 1 040337
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-20,512-00-00
NE NE SE, SEC. 31, T 28 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

2310 feet from S section line

330 feet from E section line

Operator: Knighton Oil Company, Inc.

Lease Name Brant "A" Well # 1

Name & Address 710 Petroleum Building

County Pratt 89.38

Wichita, KS 67202

Well Total Depth 2750 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Halliburton Services License Number

Address

Company to plug at: Hour: 10 a.m. Day: 20 Month: 10 Year: 19 89

Plugging proposal received from Carl Gilpin

(company name) Knighton Oil Company, Inc. (phone) 913-625-6702

were: 4 1/2" at 2745' PBD 2708' Perfs at 2628-2638, 2624-2628' Elevation 1821' GL

1st plug pump 100 lbs. hulls, 20 sx cement, 9 sx gel, 100 sx cement down 4 1/2"

RECEIVED

2nd plug pump 100 sx cement down 8 5/8" X 4 1/2" annulus.

STATE CORPORATION COMMISSION

OCT 26 1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11 a.m. Day: 20 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 100 lbs. hulls, 20 sx cement, 9 sx gel and 100 sx cement.

Maximum pressure 550 psi and shut in 350 psi.

2nd plug pumped down 8 5/8" X 4 1/2" annulus with 100 sx cement. Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-30-89

INV. NO. 26270

10-20

Signed Stephen P. Pfeiffer (TECHNICIAN)