

1 010221

MAR 4 1987

15-151-00366-00-01

To:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A

SE SE SW, SEC. 29, T 28 S, R 11 W/E  
330 feet from S section line  
2970 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Brant Well # 1

Operator: Raymond Oil Company, Inc.

County Pratt

104.85

Name &amp;

Address P.O. Box 48788

Well Total Depth 3226 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well ☒ Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 4 Month: 3 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 2767' PBTD 2730' Perfs at 2602-26' Elevation 1820' GL

1st plug sand back to 2550' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 2 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Paul Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All ☒ Part None

Operations Completed: Hour: 1:50 p.m. Day: 4 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 2550' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 20 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 700 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2200' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)INVOICED  
(If additional description is necessary, use BACK of this form.)

DATE 3-20-87

Signed

  
(TECHNICIAN)

MAR 18 1987

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 16363

FORM CP-2/3  
Rev. 01-84