

2-16

To: 1 040227
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-151-21,317-00-00
C N/2 SW/4, SEC. 36, T 28 S, R 11 W/E
1980 feet from S section line
3960 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5171
Operator: TXO Production Corporation
Name & Address 1660 Lincoln Street, Suite 1800
Denver, CO 80264

Lease Name Waylon Well # 1
County Pratt 92.63
Well Total Depth 2850 feet
Conductor Pipe: Size _____ feet
Casing: Size 8 5/8 feet 396

Abandoned Oil Well _____ Gas Well Oil Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____
Plugging Contractor Clarke Corporation
Address Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:15 a.m. Day: 16 Month: 2 Year: 19 89

Plugging proposal received from Elmo Morgenstern
(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 2845' PBDT 2804' Perfs at 2654-2666'
1st plug sand back to 2600' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 125 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 10:45 a.m. Day: 16 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 2600' and dumped 4 sx cement on top of
sand through bailer,
2nd plug pumped down 8 5/8" with 400 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 750 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 2% gel 2% cc by B.J. Titan. Recovered 2021' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(if desired) observe this plugging.

DATE 2-22-89

INV. NO. 24009

2-16

Signed Stephen S. Pfeifer
(TECHNICIAN)