

To: 1 040383
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-27
API NUMBER 15-151-21,322-50-00
W/2 NE, SEC. 36, T 28 S, R 11 W/E
3960 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Allbritten Well # 1

Operator: TXO Production Corporation
Name & Address 1660 Lincoln St., Suite 1800
Denver, CO 80264

County Pratt 92.63

Well Total Depth 2850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:15 a.m. Day: 27 Month: 12 Year: 19 89

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 2849' PBD 2802' Perfs at 2640-44, 2654-58'

1st plug pump 25 sx common cement.

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 27 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" casing with 25 sx common cement,

stopped plug at 2350',

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

STATE CORPORATION COMMISSION

01-02-90 JAN 2 1990

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2200' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

Signed Stephen J. Puffer (TECHNICIAN)

DATE 1-5-90

INV. NO. 26902

12-27