

10-31

1 040181

API NUMBER 15-151-21,385 -00-06

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N/2 NW SE, SEC. 36, T 28 S, R 11 W/4
2310 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Gorges Well # 1

Operator: TXO Production Corporation
Name & Address 155 North Market, Suite 1000
Wichita, KS 67202

County Pratt 92.63

Well Total Depth 2850 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 430

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5150

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 12 p.m. Day: 31 Month: 10 Year: 19 88

Plugging proposal received from Elmo Morgenstern

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 2806' PBSD 2765' Perfs at 2652-60'

1st plug sand back to 2600' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 35 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug

and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 2 1988 11-02-88

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Wichita, Kansas All X Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 31 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2600' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 400 lbs. hulls, 35 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 2% cc, 2% gel by B.J. Titan. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 11-3-88

Signed Stephen J. Pfeifer
(TECHNICIAN)

INV. NO. 22873