

1 040442

7-23

300 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,305-00-00

C NE SE, SEC. 35, T 28 S, R 11 W/4

1980 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Bortz Well # 2

Operator: TXO Production Corporation

County Pratt 92.63

Name & Address 1660 Lincoln Street

Well Total Depth 2850 feet

Denver, CO 80264

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 421

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10:15 a.m. Day: 23 Month: 7 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 4 1/2" at 2784' PBTD 2774' Perfs at 2638-43, 2649-51'

1st plug pump 100 lbs. hulls and 25 sx cement,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 23 Month: 7 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped down 4 1/2" with 100 lbs. hulls and 25 sx cement,

stopped plug at 2500',

2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 700 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2000' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOLVED observe this plugging.

DATE 8/20/90

07-31-90

Signed Stephen J. Parfer (TECHNICIAN)

INV. NO. 28868

7-23