

To: 104.716  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

11-4  
API NUMBER 15-151-21,122-00-00 1012  
C S/2 NW, SEC. 34, T 28 S, R 11 W/8

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name:  
Address P.O. Box 48788  
Wichita, KS 67201

3300 feet from S section line  
3960 feet from E section line  
Lease Name Ford Well # 2  
County Pratt 88.56  
Well Total Depth 2725 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8" feet 248

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050  
Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 9:30 a.m. Day: 4 Month: 11 Year: 19 92

Plugging proposal received from Vernon Duntz  
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 2723' w/125 sx cement, PBTD 2661', Perfs at 2623-33'  
1st plug sand back to 2575' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100, sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 10:15 a.m. Day: 4 Month: 11 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 2570' and dumped 4 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 1000 psi and shut in 400 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1965' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did / did not) observe this plugging.  
DATE 11-24-92  
INV. NO. 36914

Signed Stephen J. Pifer  
(TECHNICIAN)