

1 010222

MAR 4 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,433-00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS 67201

NW/4 SE/4, SEC. 33, T 28 S, R 11 W/E
1980 feet from S section line
1980 feet from E section line

Lease Name Bolt Well # 1

County Pratt 89.25

Well Total Depth 2746 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 254

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 4 Month: 3 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 2726' Perfs at 2628-38' Elevation 1795' GL

1st plug sand back to 2575' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump: 125 sx cement.

Plugging Proposal Received by Jack Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 4:30 p.m. Day: 4 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 2575' and dumped 4 sx cement on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 500 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing. 03-18-87
(If additional description is necessary, use BACK of this form.) STATE CORPORATION COMMISSION

INVOICED (If applicable) observe this plugging.

DATE 3-20-87

Signed Jack Luthi (TECHNICIAN) MAR 18 1987
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 16361