

8-18-88

1 040151

API NUMBER 15- 151-20,611-00-00

C N/2 , SEC. 33 , T 28 S, R 11 W/E

3960 feet from S section line

2640 feet from E section line

Lease Name Bush Well # 2

County Pratt 89.18

Well Total Depth 2744 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 206

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.

Name & Address P.O. Box 48788

Wichita, KS 67201

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor: Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:15 a.m. Day: 18 Month: 8 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 2727' PBTD 2703' Perfs at 2594-2614' Elevation 1785'GL

1st plug sand back to 2540' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 4 sx hulls, 20 sx gel, release 8 5/8" wiper plug and pump 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION AUG 23 1988 08-23-88 CONSERVATION DIVISION Wichita, Kansas

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed Hour: 10:00 a.m. Day: 18 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2540' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 600 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2033' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

Observe this plugging.

Signed Stephen J. Pfeifer (TECHNICIAN)

INVOICED

DATE 8-24-88

INV. NO. 21891

Petro-Log

Gamma Ray

COMPANY RAYMOND OIL COMPANY, INC.

WELL BUSH #2

FIELD _____

COUNTY PRATT STATE KANSAS

Location C-3/2
 Sec. 33 Twp. 28S Rge. 11W

Other Services:
SCB

Permanent Datum: GROUND LEVEL Elev. 1785
 Log Measured From HB, 5 Ft. Above Perm. Datum
 Drilling Measured From KELLY BUSHING

Elev.: K.B. 1790
 D.F. -
 G.L. 1785

Date	2/17/79				
Run No.	ONE				
Depth—Driller	274				
Depth—Logger	2702				
Btm. Log Inter.	2702				
Top Log Inter.	1700				
Casing—Driller	8 5/8	@ 206	4 1/2 @	@	
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	WATER				
Dens.	Visc.				
pH	Fluid Loss	ml	ml	ml	ml
Source of Sample					
R ₁₀₀ @ Meas. Temp.	@	*F	@	*F	@ *F
R ₁₀₀ @ Meas. Temp.	@	*F	@	*F	@ *F
R ₁₀₀ @ Meas. Temp.	@	*F	@	*F	@ *F
Source: R ₁₀₀					
R ₁₀₀ @ BHT	@	*F	@	*F	@ *F
Time Since Circ.					
Max. Rec. Temp.		*F		*F	*F
Equip.	Location	H-1	GB		
Recorded By	ACHATZ AND JACOBS				
Witnessed By	MR. A. SCHOENHOFFER				

RECEIVED
 STATE CORPORATION COMMISSION

MAY 04 1983

CONSERVATION DIVISION
 Wichita, Kansas