

1 040150

8-18-88

API NUMBER 15-151-20,403-06-80

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

C E/2 NW, SEC. 32, T 28 S, R 11 W/4

3960 feet from S section line

3300 feet from E section line

Lease Name Armitstead Well # 1

County Pratt 90.68

Well Total Depth 2790 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 256

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Operator: Raymond Oil Company, Inc.

Name & Address P.O. Box 48788

Wichita, KS 67201

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SHD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 18 Month: 8 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 2739' PBD 2704' Perfs at 2600' Elevation 1800' GL

1st plug sand back to 2550' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1 p.m. Day: 18 Month: 8 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 2550' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,

100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2023' of 4 1/2" casing.  
(if additional description is necessary, use BACK of this form.)

**INVOICED**  
observe this plugging.

DATE 8-24-88

INV. NO. 21909

Signed Stephen J. Pfeifer  
(TECHNICIAN)

# Petro-Log

# Gamma Ray

COMPANY RAYMOND OIL COMPANY, INCORPORATED

WELL ARMITSTEAD #1

FIELD \_\_\_\_\_

COUNTY PRATT STATE KS

Location  
C-E/2-NW

Other Services:  
SONIC CEMENT  
BOND

Sec. 32 Twp. 28S Rge. 11W

Permanent Datum: GROUND LEVEL Elev. 1800  
Log Measured From K.B., 5 Ft. Above Perm. Datum  
Drilling Measured From KELLY BUSHING

Elev.: K.B. 1805  
D.F. 1802  
G.L. 1800

Date	10/12/77				
Run No.	ONE				
Depth—Driller	2730				
Depth—Logger	2734				
Btm. Log Inter.	2200				
Top Log Inter.	2000				
Casing—Driller	8 5/8 @	4 1/2 @	2739	@	@
Casing—Logger					
Bit Size	7 7/8				
Type Fluid in Hole	WATER FULL				
Dens.	Visc.				
pH	Fluid Loss	ml	ml	ml	ml
Source of Sample					
R <sub>1</sub> @ Meas. Temp.	@	'F	@	'F	@
R <sub>2</sub> @ Meas. Temp.	@	'F	@	'F	@
R <sub>3</sub> @ Meas. Temp.	@	'F	@	'F	@
Source: R <sub>1</sub> R <sub>2</sub>					
R <sub>4</sub> @ BHT	@	'F	@	'F	@
Time Since Circ.				RECEIVED	
Max. Rec. Temp.	'F			STATE CORPORATE COMMISSION 'F	
Equip.   Location	H-2	GB			
Recorded By	YANCEY			MAY 03 1983	
Witnessed By	MR. A. SCHOENBERGER				

CONSERVATION DIVISION  
Wichita, Kansas