

1 100020 15-119-19027-0001

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Docket #D-27,218 (was E-23,655)

C SE SE, SEC. 3, T 35 S, R 30 ~~XX~~  
660 feet from S section line  
660 feet from E section line

2-20

TECHNICIAN'S PLUGGING REPORT  
Operator License / 3911

Lease Name W.B. Fox Well / 2

Operator: RAMA Operating Company, Inc.  
Name  
Address P.O. Box 159  
Stafford, KS 67578

County Meade 204.10

Well Total Depth 6280 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1473

Abandoned Oil Well Gas Well Input Well SWD Well X O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address:

Company to plug at: Hour: 8:30 a.m. Day: 20 Month: 2 Year: 19 96

Plugging proposal received from Randy Sinest

(company name) Allied Cementing (phone) 316-234-5987

Work: 4 1/2" at 6270' w/300 sx cement, PBTD 6140', Perfs at 4470-4500, 4510-40, 754-815'

1st plug pump 65 sx cement at 4116' through tubing,

2nd plug pump 65 sx cement at 2000' through tubing,

3rd plug pump 25 sx cement at 1500', 4th plug pump 45 sx cement at 1500',

5th plug pump 40 sx cement at 810', 6th plug pump 10 sx cement at 40-0'.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 9:30 a.m. Day: 20 Month: 2 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug pumped 65 sx cement at 4116' through tubing

2nd plug pumped 65 sx cement at 2000' through tubing, 2-29-96

3rd plug pumped 25 sx cement at 1500',

4th plug pumped 45 sx cement at 1500'. TOC 1350',

5th plug pumped 40 sx cement at 810',

6th plug pumped 10 sx cement at 40-0'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 750' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(did / xxxxxxx) observe this plugging.

DATE MAR 06 1996

INV. NO. 44951

Signed Gary McIntosh (TECHNICIAN)

RECEIVED  
KANSAS CORP COM  
FEB 29 11:17 '96