

1100222

15-119-10248-0000

TO:

API NUMBER SPUDED 12-29-66 15-119-10248-0000

STATE CORPORATION COMMISSION

6-10

C-SE-NE SEC. 4, T 35 S, R 30 W

CONSERVATION DIVISION - PLUGGING SECTION NA 3401 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET NA 554 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ADAMS RE Twin WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY MEADE

OPERATOR LICENSE # 5225

WELL TOTAL DEPTH 6300 204.75 FEET

OPERATOR: QUINOUE OPERATING CO.

PRODUCTION CSG: SIZE 2 7/8" FEET 6296' CMT NA

NAME AND P.O. BOX 2738

SURFACE CSG 8-5/8" FEET 600

ADDRESS LIBERAL, KANSAS 67905-2738

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS/HORTON LICENSE NUMBER 6547

ADDRESS 620 SOUTH LINCOLN STREET 67901

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 10 MONTH: 6 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM ROGER PEARSON

(COMPANY NAME) QUINOUE OPERATING CO. (PHONE) 316-621-1158

WERE: CASING WAS BRIDGED OFF AT 1500'. COULD NOT GET DOWN. PULL CASING TO 1250' AND SPOT

60 SX PLUG. PULL CASING TO 600' AND SPOT 60 SX PLUG. PULL TO 60' AND FILL TO SURFACE WITH 15 SX.

PLUGGING PROPSAL RECEIVED BY: GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 10 MONTH: 6 YEAR: 1998

ACTUAL PLUGGING REPORT CASING WAS BRIDGED OFF AT 1500' COULD NOT GET PASSED THAT POINT. PULL CASING TO 1250' AND SPOT 60 SX CEMENT PLUG HERE. PULL CASING TO 600' AND SET 60 SX PLUG HERE PULL CASING TO 60' AND FILL TO SURFACE WITH 15 SX. WELL PERFERATIONS ARE FROM 6248 TO 6264.

RECEIVED
STATE CORPORATION COMMISSION

JUL 01 1998 7-1-98

CONSERVATION DIVISION
Wichita, Kansas

REMARKS: USED 135 SXS. OF ELTORO COMMOM CEMENTED BY SARGENTS. 1250' 2 7/8 RECOVERED
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED

Gary L. Winters
(TECHNICIAN)

FORM CP-2/3

INVOICED

DATE

JUL 07 1998

INV. NO.

50870