

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

MAR 5 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Casey of Yucca has this  
date requested permission to plug the following described well:

Mr. Casey guarantees payment of the plugging fee.

Operator's full Name: Yucca Petroleum Company

Complete Address: Box 2585, Amarillo, Texas

Lease Name: Krause Well No. 1

Location: C SE SE Sec. 23 Twp. 32 Rge. 31 (E)(W)

County: Seward Total Depth 6068' Oil Well

Gas Well X Input Well      SWD Well      D & A      Lost Hole     

Mr. Casey was instructed to plug the well as follows:

8 5/8" to 1671' circulated w/ cement. 5 1/2" to 6067' cemented.

Top perforations 3080' Plug bottom w/ 25 sacks cement.

Top of cement 2950' Mud 2950' to 1000'

Spotte 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent