

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION
JAN 20 1971
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Armstrong of Yucca Petro. has this

date requested permission to plug the following described well:

Mr. Armstrong guarantees payment of the plugging fee.Operator's full Name: Yucca Petroleum CompanyComplete Address: Box 2585, Amarillo, TexasLease Name: Espana Well No. 1Location: C SE SE Sec. 22 Twp. 32 Rge. 31 (E)(W)County: Seward Total Depth 6090' Oil Well Gas Well X Input Well SWD Well D & A X Lost Hole Mr. Armstrong was instructed to plug the well as follows:8 5/8" to 1630' circulated w/ cement. 2 7/8" to 4545' cemented.Top perforations 4409' Plug bottom w/ 10 sacks cementTop of cement 4000' Mud 4000' to 1000'Spot 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent