

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 7 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Hanna of Anadarko Production has this

date requested permission to plug the following described well:

Mr. Hanna guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Company

Complete Address: Box 351, Liberal, Kansas 67901

Lease Name: Evans "B" Well No. 1

Location: App C NW Sec. 36 Twp. 32 Rge. 31 (E) (W)

County Seward Total Depth 5820' Oil Well

Gas Well X Input Well  SWD Well  D & A X Lost Hole

Mr. Hanna was instructed to plug the well as follows:

8 5/8" to 1640' circulated w/ cement. 4 1/2" to 5819' cemented.

Top perforation s 5573' Plug bottom w/ 15 sacks cement

Top of cement 5000' Mud 5000' to 900'

Spotted 35 sacks cement 900' to 800' Mud 800' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

E. Edward Johnson  
Conservation Division Agent