

15-175-10138-0000

State of Kansas



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Gatlin of Anadarko Production has this date requested permission to plug the following described well:

Mr. Gatlin guarantees payment of the plugging fee.

Operator's full Name: Anadarko Production Co.

Complete Address: Box 351, Liberal, Kansas

Lease Name: Singley Well No. 1

Location: C NE SW Sec. 34 Twp. 32 Rge. 31 (E)(W)

County: Seward Total Depth 6250' Oil Well

Gas Well X Input Well      SWD Well      D & A X Lost Hole     

Mr. Gatlin was instructed to plug the well as follows:

8 5/8" to 2309' circulated w/ cement. 4 1/2" to 6083' cemented.


Top perforations 5515' Plug bottom w/ 20 sacks cement

Top of cement 4800' Mud 4800' to 600'

Spot 35 sacks cement 600' to 500' Mud 500' to 45'

Plug, Halls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent