

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

FEB 24 1971

CONSERVATION DIVISION  
Wichita, KansasVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Duncan of White Shield has this

date requested permission to plug the following described well:

Mr. Duncan guarantees payment of the plugging fee.Operator's full Name: White Shield Oil & Gas Corp.Complete Address: Box 2139, Tulsa, OklahomaLease Name: Singley "A" Well No. 34-1Location: C SW NE Sec. 34 Twp. 32 Rge. 31 (E) (W)County: Seward Total Depth 6020' Oil Well XGas Well      Input Well      SWD Well      D & A X Lost Hole     Mr. Duncan was instructed to plug the well as follows:8 5/8" to 1600' circulated w/ cement. 5 1/2" to 6010' cemented.Top perforations 5771' Plug bottom w/ 20 sacks cementTop of cement 5630' Mud 5630' to 1000'Spotted 35 sacks cement 1000' to 900' Mud 900' to 45'Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
 Conservation Division Agent