

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 3 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Dick Davis of Whitestone Pet. Corp. has this

date requested permission to plug the following described well:

Mr. Dick Davis guarantees payment of the plugging fee.

Operator's full Name: Whitestone Pet. Corp.

Complete Address: 900 Vaughn Bldg. Dallas, Texas

Lease Name: Barnum Well No. # 1

Location: NW/4 Sec. 30 Twp. 32S Rge. (E) (W) 31

County Seward Total Depth 6046' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dick Davis was instructed to plug the well as follows:

13 3/8" 560' Circulated w/cement. 8 5/8" 2291' Circulated w/cement/

4 1/2" 5651' Cemented. Plug back-5618' Top Perf. 5556'

Sand hole to 5530' 5 sax.cement 5530' to 5465'

Mud 5465' to 700' Plug and 35 sax.cement 700' to 600'

Mud 600' to 50' Rock Bridge 50' to 40'

15 sax.cement 40' to Surface.

Very truly yours,

[Signature]
 Conservation Division Agent