

15-189-10042-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 1 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sargent of Mobil has this

date requested permission to plug the following described well:

Mr. Sargent guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: George B. Strong Well No. 6

Location: G NE NW Sec. 12 Twp. 31 Rge. 35 (E) (W)

County: Stevens Total Depth 5690' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sargent was instructed to plug the well as follows:

8 5/8" to 644' circulated w/ cement. 4 1/2" to 5680' cemented.

Top perforations 5564' Plug bottom w/ 20 sacks cement.

Top of cement 5500' Mud 5500' to 644'

Spot 35 sacks cement 644' to 544' Mud 544' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

INVOICED

Very truly yours,

DATE 11/2/73

INV. NO. 8091-U


Conservation Division Agent