

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 12 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Haggett of Mobil has this

date requested permission to plug the following described well:

Mr. Haggett guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Geo. B. Strong Well No. 3

Location: C SW NW Sec. 12 Twp. 31 Rge. 35 (E) (W)

County: Stevens Total Depth 5740' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Haggett was instructed to plug the well as follows:

8 5/8" to 627' circulated w/ cement. 5 1/2" to 5739' circulated w/cement.

Top perforations 5626' Plug bottom w/ 20 sacks cement.

Top of cement 5200' Mud 5200' to 650'

Spot 10 sacks cement 650' to 550' Mud 550' to 50'

Plug, & 5 sacks cement 50' to 0'.

Very truly yours,

[Signature]
Conservation Division Agent