



# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1974

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Haggett of Mobil has this

date requested permission to plug the following described well:

Mr. Haggett guarantees payment of the plugging fee.

Operator's full Name: Mobil Oil Corporation

Complete Address: Box 1934, Oklahoma City, Oklahoma

Lease Name: Carrie Young Well No. 1

Location: C NE NE Sec. 11 Twp. 31 Rge. 35 (E) (W)

County: Stevens Total Depth 5750' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Haggett was instructed to plug the well as follows:

8 5/8" to 659' circulated w/ cement. 4 1/2" to 5745' circulated w/ cement.

Top perforations 5620' Plug bottom w/25 sacks cement.

Top of cement 5450' Mud 5450' to 650'

Spot 30 sacks cement 650' to 550' Mud 550' to 50'

Plug & 5 sacks cement 50' to 0'.

Very truly yours,

  
Conservation Division Agent